

33 34 Set a C.M. at this cor  
 4 3 Fnd. An oak post deep  
 in ground in middle of  
 old road. Heavy timber makes  
 transit work very difficult  
 Random Chaining  
 South checks with McHenry.  
 Chaining from North does  
 Not check. Many cuts make  
 over all distances shorter  
 Farmer says, owner of  
 land thought corner  
 to be dead.  
 bet C.M. 6" below  
 road surface.

has fram x-5 pks.  
 35.0 SE of 6" Hickory  
 18.5 E of 36" Cottonwood  
 58.2 SW of 16" elm  
 8.8 W of 14" S fence  
 51.1 NW of 20" aln  
 50.7 NE of 10" bur oak  
 Check further

